

19985 NW 13th Street Dunnellon, FL 34431 (352)877-9040 www.robinsonglazing.com FL License #SCC131152174

Robinson Glazing Solutions, LLC

DOLLAR TREE

MARIANNA, FLORIDA



A Glass and Glazing Proposal for:

Architect:

General Contractor:

CLARK, GEER, LATHAM & Associates, inc. 3901 Spring Hill Avenue Mobile, AL 36608

Respectfully submitted by,

Robert F. Moxham III, Pre-Construction Estimator rmoxham@robinsonglazing.com



DOCUMENTS

June 18, 2020

DOLLAR TREE MARIANNA, FLORIDA

Robinson Glazing Solutions, LLC is pleased to present our Proposal for Construction Services at the above project. Our proposal is based on the following documents:

- 1. Architectural Drawings
 - A. A-1.0, A-1.1, A-2.2, A-2.3, A-2.4, A-3.0, A-3.1, and A-4.0 DATED: 04/15/2020 Issued for Permit and Construction
 - B. "NO SPECIFICATIONS WHERE PROVIDED FOR DOWNLOAD"

SCOPE OF WORK

07 920 Joint Sealants

- 1. (81) +/- Lineal Feet, Exterior Sealant, Storefront & Entrances
 - One part, Standard Color Silicone
 - 1 Row

Exclusions to this section:

- o Cosmetic sealants
- o All other aspects of this section that do not pertain to our specific Work



SCOPE OF WORK

08 80 00 Glazed Aluminum Storefront

- 1. (301) +/- Sq/ft
 - Kawneer IR-501 Impact Insulated Non-Thermal
 - 2-1/2" x 5" Exterior Storefront
 - Class I Clear Anodized
- 2. Glazed
- Level D Large Missile, all locations
- 3. Warranty Periods
 - Material Warranty = 2 Years
 - Finish Warranty = 2 Years
 - Installation Warranty = 1 Year

Exclusions to this section:

- o Cosmetic sealants
- o Visual Mock-ups
- o Performance Mock-ups
- o 3 Coat Exotic or Metallic Kynar Pain

SCOPE OF WORK

08 80 00 Glazed Aluminum Entrances

- 1. (2) Exterior leaves
 - 2" Heavy Duty Medium Stile
 - Non-Thermal extrusions
 - 10" bottom rail
 - 9/16" LOW-E Laminated Glazing
 - · Class I Clear Anodized
- 2. Fitted with Hardware as described, below
- 3. Warranty Periods
 - Material Warranty = 2 Years
 - Finish Warranty = 2 Years
 - Installation Warranty = 1 Year

Door Schedule:

| Door# | Door type | Single/Pair | <u>Size</u> | HDWSet # | Int or Ext? | |
|-------|-----------|-------------|-------------|----------|-------------|--|
| 500 | ALUM | Pair | 6′ X 7′ | 500 | Exterior | |
| | | | | | | |
| | | | | | | |



08 80 00 Glazed Aluminum Entrances (continued).....

Hardware Set (#):

- a. BUTT HINGES
- b. MS-1850 LOCK
- c. SURFACE MOUNTED CLOSER (NHO)
- d. PUSH / PULL HANDLES
- e. THRESHOLD w/ SWEEP

- f. KEYED CYLINDER
- g. THUMBTURN

NOTE: ALL HARDWARE LISTED ABOVE IS TO BE SUPPLIED AS MANUFACTURE STANDARD AND COMPLY WITH FLORIDA PRODUCT APPROVAL TESTING.

Exclusions to this section :

- o Cosmetic sealants
- o 3 Coat Exotic or Metallic Kynar Paint
- Mag lock and Cylinder/Core
- o Card readers
- o Water resistance/Field testing of Entrances
- Wiring labor outside of our immediate framing

SCOPE OF WORK

08 80 00 Glazing

- 1. (259) Sq/Ft GL-1 at ALUMINUM STOREFRONT
 - 1-5/16" OA Thickness
 - 1/4" CLR Tp. w/ High Performance LOW-E Coating #2 Surface, 1/2" A.S., 9/16" clear H.S./ .090" PVB
- 2. (42) Sq/Ft GL-2 at ALUMINUM DOOR
 - 9/16" OA Thickness
 - 1/4" CLR Tp. w/ High Performance LOW-E Coating #2 Surface, .090" PVB Laminate, 1/4" CLR H.S.
- 3. (8) Sq/Ft GL-3 at HOLLOW METAL FRAME(by others) @ OFFICE 100
 - 1/4" OA Thickness
 - ONE WAY MIRROR
- 4. Warranty Periods
 - Warranty, Insulated Glass = (5) years
 - Warranty, Laminated Glass = (5) years

Exclusions to this section:

- o Cosmetic sealants
- Wind Borne Debris Resistance
- Heat Soaked glass
- o Argon filled units
- Interior glass of any kind



WARRANTY

- Robinson Glazing Solutions, LLC (RGS) will directly provide a workmanship warranty for the installation for the storefront, glass, and entrance for a period of one year after substantial completion.
- 2. All warranties for materials and products manufactured by others will be provided directly from the manufacturer and will be assigned to the owner to the extent they are provided to RGS.
- 3. RGS is not providing its own warranty against failure or defects in products manufactured by others. However, RGS will assist in managing these warranties should an issue arise.
- 4. Damage to any products or actions that would void a warranty caused by others not under RGS's control are not covered by RGS or any manufacturer under RGS's scope of work.

EXCLUSIONS

- 1. Permit fees
- 2. Off-hours or weekend work
- 3. Bond cost
- 4. Warranty Bond
- 5. Extended warranties
- 6. Protection of glass and metal
- 7. Field testing
- 8. Demolition
- 9. Temporary enclosures
- 10. Final cleaning
- 11. Low Iron glass of any kind
- 12. Glass Canopies or canopies of any kind
- 13. Floor Closures or Base molding
- 14. Parapet Cap Flashing
- 15. Mirrors or borrowed lite glazing framing
- 16. Interior doors
- 17. Hollow Metal frames
- 18. Louvers, Air diffusers or grilles, including those potentially glazed within Curtain Walls
- 19. Window shades, blinds or screens
- 20. Interior demising wall / partition wall closures
- 21. Window washing provisions, tiebacks, equipment, tracks or preparation for same
- 22. Signage or preps for attachment of same
- 23. Out of sequence erection
- 24. "Leapfrogging" during the erection process
- 25. Facility for off-site storage; all materials will be shipped direct to jobsite for installation
- 26. Any overtime premiums unless caused by RGS own workforce
- 27. Mockup testing (existing test reports from previously tested curtain walls will be provided)
- 28. Street closure permits and/or temporary pedestrian walkway protection

"PROPOSAL to Furnish & Install Materials Within"

Proposal, Exterior Storefront and Entrance:

\$ 31,309.00

(Excludes performance and payment bond)

Thirty one thousand, three hundred and nine dollars



Project Name: DOLLAR TREE Project Location: MARIANNA, FL


Request Date: 06/15/20 Bid Due Date: 06/17/20

Robinson Glazing Solutions, LLC

19985 NW 13th Dunnellon, FL 34431

Office: (352)877-9040

FL License #SCC131152174



1 STOREFRONT ELEVATION

A-3.0 SCALE: 1/4"=1'-0"


1-THUS
IR-501 2-1/2"x5"
Storefront Finish - CLEAR ANODIZED
Door Hardware Finish: US26D or Clear Anodized
IR 350 Medium Stile Impact Door 10" Rail
6'x7' LH Outswing

HDW # 500A

HINGES PER STOREFRONT MANUFACTURER
(BY GENERAL CONTRACTOR)
2 CLOSERS WITH STOP ARM AND DROP PLATE
2 PUSH PLATES (BY GENERAL CONTRACTOR)
2 PULL HANDLES (BY GENERAL CONTRACTOR)
1 KABA CYLINDER (SUPPLIED BY DOLLAR TREE)
1 COMMERCIAL GRADE DEADLOCK W/ THUMB
TURN ON SALES SIDE (SUPPLIED BY
GENERAL CONTRACTOR)
INACTIVE LEAF - KAWNEER CONTROLLER 2
POINT LOCKING SYSTEM

NOTE: CONTRACTOR SHALL VERIFY CLOSER DOES NOT HAVE A HOLD-OPEN FEATURE. IF CLOSER DOES, THE CONTRACTOR SHALL REPLACE WITH NEW CLOSER.

(NOTE: ALL HARDWARE TO BE MANU'F STD and COMPLY WITH FPA TESTING)




GEER o c . A



FLORIDA MARIANNA,






| PROJECT NUMBER: | 1910-60 |
|---------------------|---------|
| DRAWN BY: | MMA |
| CHECKED BY: | MMA |
| ISSUE DATE: | 4-15-20 |
| ISSUED FOR BIDS & P | ERMITS |
| STE OF FLO | dr. |

SHEET TITLE:

FLOOR PLAN

SHEET NUMBER: A-1.0




INTERIOR FLOOR PLAN

RK | GEER | LATHAM ASSOCIATES, INC.



OLLAR TREE





PROJECT NUMBER: 20104-05

DRAWN BY: TEH

CHECKED BY: MMA

ISSUE DATE: 04/15/2020

ISSUED FOR BIDS AND PERMITS


OF FLORAL M. ALDA

AR96329

SHEET TITLE:
INTERIOR FLOOR PLAN &
WALL CONSTRUCTION
TYPES

SHEET NUMBER:
A-1.1


NNESSEY 4/30/2020 2-16:36 PM H-V



CLARK | GEER | LATHAM AND ASSOCIATES, INC.



MARIANNA, FLORIDA



| PROJECT NUMBER: | 1910-60 |
|----------------------|---------|
| DRAWN BY: | MMA |
| CHECKED BY: | MMA |
| ISSUE DATE: | 4-15-20 |
| ISSUED FOR BIDS & PE | RMITS |
| ARG6529 | 4-15-20 |

SHEET TITLE:

EXTERIOR ELEVATIONS

SHEET NUMBER:


A-2.0

OFFICE ELEVATION

SCALE: 3/8" = 1'-0"

A OFFICE ELEVATION

A-2.3 SCALE: 3/8" = 1'-0"




CLARK | GEER | LATHAM AND ASSOCIATES, INC.
3901 SPRING HILL AVENUE | MOBILE, AL 36608 | 251344 7073



DOJUMA FLORIDA





PROJECT NUMBER: 20104-05

DRAWN BY: TEH

CHECKED BY: MMA

ISSUE DATE: 04/15/2020

ISSUED FOR BIDS AND PERMITS

OF FLOOD


RK M. ALDR


SHEET TITLE:

OFFICE DETAILS &
ELEVATIONS

SHEET NUMBER:

A-2.3





A-2.4 SCALE: 3/4" = 1'-0"

A-2.4 SCALE: 3/4" = 1'-0"


A-2.4 SCALE: 1 1/2" = 1'-0"

CLARK | GEER | LATHAM AND ASSOCIATES, INC. 3901 SPRING HILL AVENUE | MOBILE, AL 36608 | 251344 7073



DOLLAR TRE






| PROJECT NUMBER: | 20104-05 |
|--------------------|------------|
| DRAWN BY: | TEH |
| CHECKED BY: | MMA |
| ISSUE DATE: | 04/15/2020 |
| ISSUED FOR BIDS AN | D PERMITS |
| AR96329 | |

SHEET TITLE:

TOILET ROOM DETAILS &
ELEVATIONS

SHEET NUMBER:


A-2.4




ARK | GEER | LATHAM
D ASSOCIATES, INC.



OLLAR TRREE





| 7 | \vee | \vee | <u>~</u> |
|----------|-----------|-------------------|--|
| | | | |
| PROJEC: | T NUMBER | £ | 1910-60 |
| DRAWN | BY: | | MMA |
| CHECKE | DBY: | | MMA |
| ISSUE DA | ATE: | | 4-15-20 |
| ISSUE | ED FOR BI | DS & PERI | MITS |
| W.S. | LE OF | FLORILL ALDREN | A STATE OF THE PARTY OF THE PAR |

SHEET TITLE:

STOREFRONT ELEVATIONS
& DETAILS

A-3.0

| DOORS | | | DOOR | DE | TAILS | | FIRE | HDW | FRM | DOOR | | |
|-------|----------|-------|--------|---------------|-------|----------|----------|----------|------|-------|----|-------------|
| # | W | I | Τ | MATERIAL | EL | HEAD | JAMB | SILL | RATE | NOTES | EL | NOTES |
| 100 | 3'-0" | 6'-8" | 1 3/4" | SOLID CORE WD | D | 3/A-3.1 | 3/A-3.1 | - | | 100A | D | 4 |
| 200 | PR 3'-0" | 7'-0" | 1 3/4" | HOLLOW METAL | С | 3/A-3.1 | 3/A-3.1 | - | 1 HR | 200A | Е | 2,6,8,12,13 |
| 300 | 3'-0" | 6'-8" | 1 3/4" | SOLID CORE WD | D | 1/A-3.1 | 1/A-3.1 | - | | 300C | D | 4,5,11 |
| 400 | PR 3'-0" | 7'-0" | 1 3/4" | HOLLOW METAL | С | H1/A-2.0 | J1/A-2.0 | 2/A-3.1 | | 400A | С | 3,4,10 |
| 401 | 3'-0" | 7'-0" | 1 3/4" | HOLLOW METAL | В | H1/A-2.0 | J1/A-2.0 | 2/A-3.1 | | 400C | В | 3,4,7,10 |
| 500 | PR 3'-0" | 7'-0" | 1 3/4" | STOREFRONT | А | H2/A-3.0 | J3/A-3.0 | T1/A-3.0 | | 500A | Α | 1,9,10 |

DOOR NOTES

- PROVIDE A SIGN POSTED ON THE EGRESS SIDE, ON OR ADJACENT TO THE DOOR STATING: "THIS DOOR TO REMAIN UNLOCKED WHEN BUILDING IS OCCUPIED." THE SIGN SHALL BE IN LETTERS 1" HIGH ON A CONTRASTING BACKGROUND.
- 2. NEW DOORS SUPPLIED BY DOLLAR TREE W/ PRE-INSTALLED BRUSHED ALUM COVER PLATE ON SALES AREA SIDE OF THE DOOR.
- 3. PROVIDE (ONE) PEEP HOLE TO VIEW OUT. MOUNT @ 4'-3" AFF.
- 4. PAINT DOOR AND FRAME W/ WHITE SEMI-GLOSS ENAMEL PAINT. FOR DOORS 400 & 401 PAINT INTERIOR WHITE AND SEE SHEET
- A-2.0 FOR EXTERIOR COLOR. . INSTALL DOLLAR TREE SUPPLIED SIGNAGE PER DETAIL A/A-3.1.
- REINFORCE JAMBS WITH WOOD BLOCKING.
- 7. PROVIDE SIGNAGE THAT READS "EMERGENCY EXIT ONLY."
- B. PROVIDE SIGNAGE THAT READS "EMPLOYEES ONLY."
- 9. PROVIDE HANDICAPPED ACCESSIBILITY DECAL, SEE DETAIL A/A-2.6.
- 10. CONTRACTOR TO PROVIDE AND INSTALL DOOR SWEEP ON ALL EXTERIOR DOORS TO PREVENT WATER, WIND AND DEBRIS INFILTRATION.
- 11. PROVIDE COAT HOOK AT 48" AFF. ON BACK SIDE OF DOOR.
- 12. PAINT DOOR FRAME WHITE WITH SEMI-GLOSS ENAMEL PAINT. DOOR TO REMAIN WITH ORIGINAL
- 13. PROVIDE "C" LABEL DOOR AND FRAME PER UNDERWRITER'S LABORATORIES INC.

GENERAL HARDWARE NOTES:

- THRESHOLDS AT EGRESS DOORS SHALL BE NO MORE THAN 1/2" (MAX) HEIGHT AFF.
- 2. ALL DOOR HANDLES, PULLS, LATCHES, LOCKS AND OTHER OPERATING DEVICES SHALL BE INSTALLED 34" (MIN) TO 48" (MAX) AFF AND SHALL BE "SINGLE-HANDED" OPERABLE WITHOUT USE OF KEY OR SPECIAL KNOWLEDGE.
- WHERE EGRESS DOORS ARE USED IN PAIRS, THE UNLATCHING OF THE LEAF SHALL NOT REQUIRE MORE THAN ONE (1) OPERATION AS MENTIONED IN GENERAL HARDWARE NOTE #2 ABOVE.
- CONTROLS AND OPERATING MECHANISMS SHALL BE LEVER-TYPE (OR EQUAL) PROVIDING OPERATION WITH ONE HAND AND NOT REQUIRE TIGHT GRASPING, PINCHING, OR TWISTING OF THE WRIST.
- THE FORCE REQUIRED TO ACTIVATE CONTROLS OF INTERIOR HINGED DOORS SHALL BE NO GREATER THAN 5 POUNDS (22.2 N).
- 6. DOORS EQUIPPED WITH CLOSERS SHALL BE ADJUSTED SO THAT THE SWEEP PERIOD FROM AN OPEN POSITION OF 70 DEGREES WILL TAKE AT LEAST 3 SECONDS TO MOVE TO A POINT 3" FROM THE LATCH, MEASURED FROM THE LEADING EDGE OF THE DOOR.
- REQUIRED EXIT DOORS SHALL BE OPENABLE FROM THE INSIDE WITHOUT THE USE OF A KEY, TOOL. SPECIAL KNOWLEDGE OR EFFORT. MANUALLY OPERATED FLUSH BOLTS ARE PROHIBITED. ALL HARDWARE MUST BE DIRECT ACTING REQUIRING NO MORE THAN ONE OPERATION. DOUBLE CYLINDER DEAD BOLTS, REQUIRING A KEY FOR OPERATION ON BOTH SIDE, ARE PROHIBITED ON REQUIRED MEANS OF EGRESS DOORS UNLESS THE LOCKING DEVICE IS PROVIDED WITH A KEY WHICH CANNOT BE REMOVED WHEN THE DOOR IS LOCKED FROM THE INSIDE.

| | FINISH SCHE |
|---------|---------------|
| OOR | SPACES |
| OTES | SALES |
| | STOCKROOM |
| 8,12,13 | EMPLOYEE AREA |
| 11 | OFFICE |
| 10 | TOILET |
| 7,10 | HALLWAY |
| 10 | |

HARDWARE NOTES

HDW # 100A 1 1/2 PAIR HINGES: STANDARD WEIGHT 1 MECHANICAL PUSH BUTTON LOCKSET

- WITH LEVER HANDLE
- 1 CLOSER 1 FLOOR STOP

HDW # 200A

- 3 PAIR HINGES: 4 1/2" HEAVY WEIGHT, BALL BEARING PINS
- 2 CLOSERS 1 COORDINATOR
- 1 PUSH PULL LATCH SET
- 1 SET AUTOMATIC FLUSH BOLTS (ON INACTIVE
- LEAF)
- 1 DUSTPROOF STRIKE 1 STEEL ASTRAGAL
- 1 THRESHOLD (1/4" MAXIMUM HEIGHT) 1 SMOKE SEAL
- HDW # 300C

HARDWARE)

- 1 1/2 PAIR HINGES: STANDARD WEIGHT 1 PRIVACY SET WITH LEVER HANDLE
- 1 CLOSER (FLOOR/WALL STOP IF SHIPPED WITH

HDW # 400A

- 3 PAIR HINGES: 4 1/2" HEAVY WEIGHT,
- NON- REMOVABLE PINS 1 NON-ALARMED, NON-KEYED PANIC BAR DEVICE: WITH STAND ALONE ALARM
- REFER TO DOOR ALARM MOUNTING DETAIL
- 2 OVERHEAD HOLDERS/STOPS (MAX 90°)
- 2 FLUSH BOLTS (ON INACTIVE LEAF)
- 1 DUST PROOF STRIKE 1 PEEP HOLE
- 1 ALUM THRESHOLD (1/2" MAX HEIGHT)
- 2 SWEEPS 1 WEATHER STRIP
- 1 RAIN DRIP
- 1 DOOR STOP

1 ASTRAGAL HDW # 400C

- 1 1/2 PAIR HINGES: STANDARD WEIGHT, NON- REMOVABLE PINS
- 1 NON-ALARMED, NON-KEYED PANIC BAR DEVICE: WITH STAND ALONE ALARM REFER TO DOOR ALARM MOUNTING
- DETAIL. 1 CLOSER WITH STOP ARM
- 1 PEEP HOLE 1 ALUM THRESHOLD (1/2" MAX HEIGHT)
- 1 WEATHER STRIP

1 RAIN DRIP

- HINGES PER STOREFRONT MANUFACTURER (BY GENERAL CONTRACTOR) 2 CLOSERS WITH STOP ARM AND DROP PLATE 2 PUSH PLATES (BY GENERAL CONTRACTOR) 2 PULL HANDLES (BY GENERAL CONTRACTOR) 1 KABA CYLINDER (SUPPLIED BY DOLLAR TREE) 1 COMMERCIAL GRADE DEADLOCK W/ THUMB
- TURN ON SALES SIDE (SUPPLIED BY GENERAL CONTRACTOR) INACTIVE LEAF - KAWNEER CONTROLLER 2

POINT LOCKING SYSTEM

NOTE: CONTRACTOR SHALL VERIFY CLOSER DOES NOT HAVE A HOLD-OPEN FEATURE. IF CLOSER DOES, THE CONTRACTOR SHALL REPLACE WITH NEW CLOSER.

FINISH SCHEDULE **CEILING** NOTES **FLOORS BASES** WALLS POLISHED CONCRET 4" VINYL **GWB-PAINT YELLOW** ACT 1,2,3,4,5,7,9,11,13 / FRP **ENTRY CARPET TILE** CONCRETE 4" VINYL GWB 2,9,14 5,12 CONCRETE GWB / PLYWOOD 4" VINYL **GWB-PAINT WHITE** 2,3,4,5,7,8 POLISHED CONCRET 6" SHEET VINYL FRP WB-PAINT WHITE 4,5,6,7,9,10 SHEET VINYL POLISHED CONCRETE GWB-PAINT WHITE ACT 2,3,5,9,11 4" VINYL FRP

FINISH NOTES

- CARPET TILE: MANUFACTURED BY INTERFACE FLOORING SYSTEMS AND SUPPLIED BY DOLLAR TREE. INSTALL TILES QUARTER TURNED AND PER DOLLAR TREE'S CRITERIA ENTRY TILE: DECO RIB, STYLE #678609900. CONTRACTOR SHALL PREPARE FLOOR SURFACE AND COORDINATE CARPET
- 2. VINYL COVE BASE: COLOR BLACK. (VINYL BASE ONLY ON EXPOSED WALLS NOT COVERED BY GONDOLAS IN SALES AREA.) VINYL COVE BASE TO BE LOCATED IN STOCKROOM AT MOP SINK AND CABINET ONLY UON.
- POLISHED CONCRETE FLOOR ON SALES FLOOR AND OFFICE. POLISHED CONCRETE FLOOR BY DOLLAR TREE'S VENDOR, COORDINATE WITH DOLLAR TREE,
- 4. SLATWALL: 3/4" SLATWALL WITH WHITE MELAMINE FINISH. SEE MANUFACTURER'S DRAWINGS FOR INSTALLATION DETAILS.

INSTALLATION W/ CARPET INSTALLER.

5. PAINT COLORS ARE AS FOLLOWS:

SHERWIN WILLIAMS PRO 200 LATEX WHITE -SEMI-GLOSS WHITE W/ B-1 PER GALLON.

YELLOW -BENJAMIN MOORE PRODUCT 274

"LEMON SORBET" #2019-60 (EGGSHELL FINISH)


FOREST GREEN -BENJAMIN MOORE PRODUCT 274


"FOREST GREEN" #2047-10 (EGGSHELL


"ROCKY RIVER" #SW6215 SHERWIN


WILLIAMS (SEMI GLOSS)

- 6. PAINT TOILET ROOM EXTERIOR WALLS WHITE.
- 7. SLATWALL SHALL BE PROVIDED BY DOLLAR TREE AND INSTALLED BY CONTRACTOR. ALL OTHER FINISHES SHALL BE PROVIDED AND INSTALLED BY CONTRACTOR.
- 8. PROVIDE PREFORMED COUNTER WITH WHITE HIGH PRESSURE LAMINATE FINISH. MOUNT TO WALLS. FILING CABINETS PROVIDED BY DOLLAR TREE. SEE ENLARGED OFFICE PLAN AND OFFICE ELEVATION.
- 9. F R P (FIBERGLASS REINFORCED PANEL): IN TOILET ROOM FROM 6 1/2" AFF TO 8'-0" AFF SHALL BE WHITE" COLOR (IN STOCKROOM BEHIND MOP SINK / UTILITY CABINET ONLY, IN HALLWAY BEHIND DRINKING FOUNTAIN ONLY FRP GOES FROM FINISHED FLOOR.) FRP ON SALES FLOOR (WHERE NOTED ON PLANS/ELEVATIONS) SHALL BE ALMOND COLOR WITH "J" CHANNEL TRIM CAP AND "H" CHANNEL PANEL CONNECTORS.
- 10. SHEET VINYL: CLASSIC CORLON SERIES MANUFACTURED BY ARMSTRONG -CONNECTION CORLON "PORCELAIN" #88724 OR EQUAL. SHEET VINYL BASE: BY INTREGAL, 3/8" RADIUS, 6" HIGH COVED BASE W/ COVE STICK AND EXTRUDED ALUMINUM CAP TRIM.
- 11. PROVIDE 2'-0" X 4'-0" CEILING TILE BY ARMSTRONG "CORTEGA" SQUARE LAY- IN #769, WHITE, IN A WHITE METAL GRID. (IN AREAS WITH SIGNIFICANT AIR PRESSURE DIFFERENTIALS PROVIDE RETENTION CLIPS TO RETAIN PANELS IN PLACE.)
- 12. PAINT EMPLOYEE AREA WALLS TO 4'-0" AFF "FOREST GREEN".
- 13. SALES AREA TO RECEIVE LEVEL 5 FINISH, PROVIDE FINISH TO 1'-0" BEHIND FREEZER / COOLER AND GONDOLA, TO FINISHED FLOOR EVERYWHERE ELSE. CONTRACTOR SHALL ALLOW 72 HOUR CURE TIME.
- 14. PAINT 6" WIDE BAND ON CONCRETE FLOOR AROUND PERIMETER OF STOCKROOM WITH 2 COATS BENJAMIN MOORE "FD BM WHITE" TOUGH SHIELD ACRYLIC GLOSS TY-43. PAINT BAND PRIOR TO PAINTING ANY YELLOW CLEAR FLOOR SPACE AREAS.











DOOR FRAME ELEVATIONS

SCALE: 1/4" = 1'-0"





SHEET TITLE: **INTERIOR DOOR & FINISH** SCHEDULE & DETAILS

ISSUED FOR BIDS AND PERMITS

PROJECT NUMBER:

04/15/2020

DRAWN BY:

CHECKED BY:

ISSUE DATE:

Z

H


7----

RID,

0

SHEET NUMBER:

A-3.








LAB TRB 官員





| 7 7 7 7 | V 14 |
|----------------------------------|---------|
| | |
| PROJECT NUMBER: | 1910-60 |
| DRAWN BY: | MMA |
| CHECKED BY: | MMA |
| ISSUE DATE: | 4-15-20 |
| ISSUED FOR BIDS & F | PERMITS |
| OF FLO SIN M. ALDR AR96329 | |

SHEET TITLE:

WALL SECTIONS

SHEET NUMBER:

A-4.0

06/18/20

Markup Report

1:47:39 PM

Bid Date: 06/18/20 Vendor: Kawneer 2010 r3

Estimator: Robert Moxham

Job Name: DOLLAR TREE - Marrianna FL

Contractor:

Job Contact:Phone:Phone:Fax:

Fax: Address1: Address2: Address3:

Architect: Addr1: Contact: Addr2: Phone: Addr3:

Fax:

| Material | | Labor | | Markup | |
|---------------------|-------------|----------------------------------|----------------------|--------------------------|-------------|
| Stock | \$4,289.00 | Job Labor: | \$3,443.40 | Metal and Misc % | |
| Misc: | \$0.00 | Add to Labor: | \$2,480.00 | Glass Markup % | |
| Doors: | \$2,000.00 | Total Labor: | \$5,923.40 | Other Material % | |
| Added Material: | \$1,950.00 | | . , | Labor Markup % | |
| Total Metal: | \$8,239.00 | Outside Costs | | Calculated Totals | |
| Metal Surcharge | | Subcontractor Costs: | \$700.00 | Total Material: | \$13,729.31 |
| 10 % | \$823.90 | Equipment Rental: Miscellaneous: | \$0.00 \$1,285.68 | Material Markup: | \$5,491.72 |
| Total w/Surcharge | \$9,062.90 | Total Outside: | \$1,985.68 | Total Ouside Costs: | \$1,985.68 |
| Glass: | \$4,281.11 | | V 1,000.00 | Outside Markup: | \$794.27 |
| Glass Surcharge | | Tax | | Total Labor: | \$5,923.40 |
| 9 % | \$385.30 | Metal and Misc Tax % | 7 | | |
| Total w/Surcharge | \$4,666.41 | Glass Tax % | 7 | Labor Markup: | \$2,369.36 |
| · · | | Outside Tax % | 7 | Markup Subtotal: | \$8,655.36 |
| Total Material: | \$13,729.31 | Labor Tax % | 0 | Pre-Tax Total: | \$30,293.75 |
| | | Surcharge Tax % | 0 | Sales Tax: | \$1,015.41 |
| Price per Square F | oot | | | | Ψ1,010.11 |
| Total Perimeter Ft: | 81 | Cost / Square Ft: | \$71.89 | Job Grand Total: | |
| Total Square Ft: | 301 | Sell / Square Ft: | \$104.02 | | \$31,309.16 |

Sections Bid:

DIV 08 41 00 Aluminum Entrances & Storefront

DIV 08 71 00 Door Hardware

DIV 08 80 00 Glazing

Exclusions:

"STANDARD PROPOSAL EXCLUSION APPLY"

INCLUSION(S):....

Clear Anodized IR-501 impact non-thermal

Clear Anodized IR-350 open for 9/16" and Hardware per SET 500 & FPA

06/18/20 Markup Report

1:47:39 PM

Bid Date: 06/18/20 Vendor: Kawneer 2010 r3

Estimator: Robert Moxham

Job Name: DOLLAR TREE - Marrianna FL

Contractor:

Job Contact: Phone: Fax:

Fax: Address1: Address2: Address3:

Architect: Addr1: Contact: Addr2: Phone: Addr3:

Fax:

1-5/16" CLR Lamnited w/low-e on #2 temp/hs/.090/hs

9/16" CLR Lamnited w/low-e on #2 temp/.090/hs

1/4" oneway mirror installed into HM frame

1/4" mirrors installed at mens/womens bathroom sink

Notes:

#1. FGD QUOTE TOTAL - \$6289, BROKEN DOWN ON QUOTE STOCK MATERIAL: \$4289 / DOOR MATERIAL: \$2000

#2. NO GLASS QUOTE RECIEVED PRIOR TO BID USED THE FOLLOWING \$16 1-5/16 LOW-E CLR and \$12 9/16" LOW-E CLR

#3. ADD TO LABOR: (\$2480 total)

- a.) travel time 8hrs x2men @\$35 / hr x 4 trips total \$2240
- b.) install mirror in bathroom and one-way mirror in HM frame 3hrs x 2men @\$40 \$240

#4 Outside cost/ MISC:(\$1285.68)

- a.) hotel 2 nights \$300
- b.) perdim 2 men 2 nights \$50 ea men / day \$200
- c.) mileage / gas 4 trips at 424 ea trip 1669 total miles @\$0.58 per mile \$983.68
- #5. Other materials: (\$1950)
 - a.) \$800 closers(2)
 - b.) \$500 for 2 pieces of mirror over sink & 1piece one way glass in hm frame
 - c.)\$560 80 "exterior only" lineal feet at \$7 / foot, \$45 screws, & \$45 for shims. \$650

Final Labor Report

06/18/20 1:18:43 PM

Job Name: DOLLAR TREE - Marrianna FL

Vendor: Kawneer 2010 r3

Phone:

321-419-6703

Fax:

| Elevation | Qty | Fab Hours | Frame Fab | Ent Fab Hours | Ent Fab | Misc Hours | Misc | Install Hours | Frame Install | Entr Hours | Entrance Install | Glaze Hours | Glazing | Totals |
|---------------|-------|--------------|--------------|------------------|------------|---------------|-----------|------------------|------------------|---------------|---------------------|----------------|------------|------------|
| 1/A3.0 | 1 | 15.08 | \$678.75 | 0.00 | \$0.00 | 0.00 | \$0.00 | 20.00 | \$900.00 | 7.00 | \$315.00 | 29.99 | \$1,049.65 | \$2,943.40 |
| Grand Totals: | 1 | 15.08 | \$678.75 | 0.00 | \$0.00 | 0.00 | \$0.00 | 20.00 | \$900.00 | 7.00 | \$315.00 | 29.99 | \$1,049.65 | \$2,943.40 |
| | | | Added | Job Lab | or Details | . | | | | _ | Added Jo | b Labor: | | \$500.00 |
| Item Descri | ption | | | | | | Misc Hour | s Fix | ed Amount | | Job Grand | d Total: | | \$3,443.40 |
| Layout | | | | | | | | | \$500.00 | | | | | |

Area Vent:

Job Name: DOLLAR TREE - Marrianna FL

.00

\$.00

Phone: 321-419-6703

Email: rmoxham@robinsonglazing.co

| | | | | | | | Min | t | :maii: rm | oxnam@robir | obinsonglazing.co | |
|------------------------|---------------|--------|----------|--------|---------------|-------|------|-------------|------------------|-------------|-------------------|------------|
| | | Glass | | | Block | | Min | Area | Area | Area | Area | |
| Qty Type | Category | Thick | Width | Height | Size | Rake? | Area | OK? | Each | Price | Total | Totals |
| 1-5/16"LOW-E CLEAF | R | | | | | | | | | | | |
| Annealed | | | | | | | | | | | | |
| 6 Annealed | panel glass | 1.3125 | 46 3/16 | 45 5/8 | 48 x 46 | | 3 | | 15.33 | \$16.00 | 92.00 | \$1,472.00 |
| 6 Annealed | panel glass | 1.3125 | 46 3/16 | 67 5/8 | 48 x 68 | H | 3 | 2 | 22.67 | \$16.00 | 136.00 | \$2,176.00 |
| 1 Annealed | transom glass | 1.3125 | 73 | 31 5/8 | 74 x 32 | _ | 3 | | 16.44 | \$16.00 | 16.44 | \$263.11 |
| 13 | | | | | | | | | | | 244.44 | \$3,911.11 |
| 9/16" LOW-E CLEAR | | | | | | | | | | | | |
| Annealed | | | | | | | | | | | | |
| Annealed | | | | | | | | | | | | |
| 2 Annealed | door glass | 0.5625 | 29 | 74 | 30 x 74 | | 3 | > | 15.42 | \$12.00 | 30.83 | \$370.00 |
| 2 | | | | | | | | | | | 30.83 | \$370.00 |
| | | | | Fii | nal Glass Tot | als: | | | | | 275.28 | \$4,281.11 |
| Misc. Glass Totals: | | | | | | | | | | | | |
| All Lites: | 15 | | | | | | | | | | | |
| Perimeter of All Glass | s: 257.00 |) | | | | | | | | | | |
| Lites without Doors: | 13 | } | | | | | | | | | | |
| Area Annealed: | 244.44 | · \$: | 3,911.11 | | | | | | | | | |
| Area Heat Strengther | | | \$.00 | | | | | | | | | |
| Area Tempered: | .00 |) | \$.00 | | | | | | | | | |
| Area Spandrel: | .00 | | \$.00 | | | | | | | | | |
| Area Panels: | .00 | 1 | \$.00 | | | | | | | | | |

Area Miscellaneous: .00 \$.00 Area Door Lites: 30.83 \$370.00

Note: Glass is priced by Block Size.